BANGALORE DIVISION.

ADVERTISEMENT.

The 19th October 1886.

Tenders are hereby invited for the restoration of Yennagere Tank, Registered No. 187, Magadi Taluk.

2. The plan and detailed estimate and conditions may be seen at the Executive Engineer's Office, Bangalore Division, between the hours of 11 A. M. and 4 P. M. daily.

3. The following is the form of tender which should be copied out and the blank columns for rates, cost and total filled in, item by item, signed by the contractor and forwarded in sealed covers to the Executive Engineer before the 1st November 1886.

Form of Tender.

4. I hereby tender for the execution of all work necessary for the restoration of the Yennagere Tank, Registered No. 187, Magadi Taluk, at the rates entered opposite to each item in the accompanying bill of quantities, and in accordance with the usual sanctioned plans, conditions, &c :—

Items of Work.	Per.	Quantity.	Rate.	Cost.	Total of each.	Grand Total.
Earthwork filling including watering and tamping	C. yd.	5,000				
Do excavation and refilling ..	,,	372				
Do cutting	,,	1,110				
New stone work revetment	,,	814				
Old stone work with new jelli ..	,,	610				
Grade stones	No.	13				
B. M. stones	,,	2				
Turfing front slope	S. yd.	791				
Brick in chunam	C. ft.	1,102				
Slabs	S. ft.	269				
Plastering with chunam ..	Sqr.	4·72				
Dismantling old sluice and removing debris	Item.	1				
Removing and re-setting gibbets and cross stones, &c.	,,	1				
Stepping rock for body wall.. ..	,,	1				
New stone work, sujikat	C. yd.	15				

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. No tenders will be received unless accompanied by a deposit of Rs. 25 as earnest money.

7. Within 8 days of the acceptance of the tender the contractor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be taken to meet any loss that may be sustained by Government.

8. The name of the contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

9. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicant in due course.

Note.—This tank is situated two miles to the north of 24th mile, Nelamangala-Solur Road.

T. INMAN,
Executive Engineer.